

<b>BMPs</b>	<b>CASQA Handbook</b>	<b>Caltrans Handbook</b>
Stabilized Construction Entrance/ Exit	TC-1	TC-1
Stabilized Construction Roadway	TC-2	TC-2
Entrance/ Exit Tire Wash	TC-3	TC-3
<b>Non-Storm Water Management</b>		
Vehicle and Equipment Washing	NS-8	NS-8
Vehicle and Equipment Fueling	NS-9	NS-9

3. BMP Implementation - Construction Sites 5 acres and Greater
- (a) Each Permittee shall require the implementation of an effective combination of the following BMPs in Table 8 (BMPs at Construction sites 5 acres or greater) in addition to the ones identified in Table 6 (BMPs at Construction sites less than 1 acre) and Table 7 (BMPs at Construction sites 1 acre or greater but less than 5 acres) at all construction sites 5 acres and greater to prevent erosion and sediment loss, and the discharge of construction wastes. Erosion control BMPs shall be preferred to sediment control BMPs.

Table 8 - BMPs at Construction sites 5 acres or greater

<b>BMPs</b>	<b>CASQA Handbook</b>	<b>Caltrans Handbook</b>
<b>Sediment Controls</b>		
Sediment Basin	SE-2	SC-2
Check Dam	SE-4	SC-4
<b>Tracking Control BMPs</b>		
Stabilized Construction Entrance/ Exit	TR-1	TC-1
<b>Non-Storm Water Management</b>		
Vehicle and Equipment Maintenance	NS-10	NS-10
<b>Waste Management</b>		
Material Delivery and Storage	WM-1	WM-1
Spill Prevention and Control	WM-4	WM-4
Concrete Waste Management	WM-8	WM-8
Sanitary/ Septic Waste Management	WM-9	WM-9